

6 Step Lorry Access

Product Overview

Z/STEP/LORRY/6



Step Width

500mm - Standard
850mm - Wide

Options

Rubber Wheels
RUGGED Wheels
Galvanized
Bottom Gate
Rear Safety Bar
Climb Prevention Bar
Swing Out Rear Stabilisers
Front Levelling Legs

VAT Not Included
Free Delivery

Mobile Steps lead time is generally 7 days. Whilst we stock the step components, the mobile steps are built to order. We would typically allow 3 days to build the steps, a day to paint them and then despatch the mobile ladders on a 3 day service.

| Specification | | |
|-----------------------------|-----------------------------|-------------------------|
| Dimensions | Standard Step Width (550mm) | Wide Step Width (850mm) |
| Platform Height From Ground | 1500mm | 1500mm |
| Overall Length | 1400mm | 1400mm |
| Overall Height | 2500mm | 2500mm |
| Overall Axle Width | 1150mm | 1450mm |
| Platform Size | 550mm x 380mm | 850mm x 380mm |
| Step Tread Width | 550mm x 200mm | 850mm x 200mm |
| Step Tread Vertical Spacing | 250mm | 250mm |
| Weight Standard Width | 62kg | |
| Load Capacity | 300kg | 300kg |

- Fitted with 2 substantial 200mm nylon wheels and 2 smaller 100mm diameter wheels housed in swivel castors allowing easy movement
- On the side is mounted a brake lever which disengages the smaller wheels when in use allowing a safe stable platform
- Also fitted is a safety rail at the top and safety notice on the side.
- There are 2 lever brakes mounted within the structure which disengage each pair of wheels.
- Mobile steps are painted as standard using a one coat primer/finish - Zinfos 700CT, or can be galvanized.